ANEXO 2: CAR-SIP-093-2024
GRUPO 3 - MET ONE

NOMBRE O RAZON SOCIAL	**SANAMBIENTE SAS**	**NIT**	**80500004-1**
RESPONSABLE O ENCARGADO	**JAIME OMAR DIAZ**	**NUMERO DE COTIZACIÓN**	**PR-20-09-2024**
CORREO ELECTRÓNICO	**ventas@sanambiente.com.co**	**TELEFONO DE CONTACTO**	**3148881477**

OBJETO: Adquisición de insumos y repuestos para la operación y mantenimiento de los equipos que componen la red de calidad del aire y olores ofensivos de la Corporación Autónoma Regional de Cundinamarca CAR

ITEM	EQUIPO/SUMINISTRO/SERVCIO	CARACTERSITICAS	OTRAS CONSIDERACIONES (SI APLICA) COMO UNIDADES O CANTIDADES TOTALES U OTRA	CANTIDAD (A)	VALOR UNITARIO (B)	TARIFA IVA (%)	VALOR IVA (C)	VALOR TOTAL A*(B+C)
1	CONSUMIBLES - BAM1020	Filter Tape Roll, Glass Fiber, 70+ days per roll 30mm x 25m	460180	29	$ 682.535	19%	$ 129.682	$ 23.554.266
2	CONSUMIBLES - BAM1020	Cotton-Tipped Applicators, nozzle cleaning, 100 pack Solon #362	995217	94	$ 119.743	19%	$ 22.751	$ 13.394.440
3	CONSUMIBLES - BAM1020	Silicone O-Ring Grease, mini packets	995712	16	$ 27.633	19%	$ 5.250	$ 526.132
4	CONSUMIBLES - BAM1020	BAM Inlet Cleaning Kit Includes pull-rope, tube brush, microfiber rags, cleaning brushes, O-ring grease, cotton applicators. For cleaning inlet tube and PM10, PM2.5 inlets	BX-344	16	$ 831.292	19%	$ 157.945	$ 15.827.800
5	CONSUMIBLES - BAM1020	Muffler, Medo/Gast Pump, Replacement	580293	14	$ 64.477	19%	$ 12.251	$ 1.074.186
6	CONSUMIBLES - BAM1020	Gast Pump Rebuild Kit. Vanes, filters.	680828	5	$ 1.694.823	19%	$ 322.016	$ 10.084.194
7	CONSUMIBLES - BAM1020	Pump Service Kit, Filter Replacement, Medo	8588	16	$ 340.807	19%	$ 64.753	$ 6.488.960
8	CONSUMIBLES - BAM1020	Filter Element Only, Pisco In-line	580292	16	$ 165.798	19%	$ 31.502	$ 3.156.791
9	REPUESTOS- BAM1020	BAM 1020 Distributor Service Tool Kit: Includes all (Includes nozzle shims, reel spacer, filter sensor removal tool, darkst shim, rubber leak check tool, hex wrenches.) of the above plus two spring scales.	BX-308-1	16	$ 2.712.637	19%	$ 515.401	$ 51.648.612
10	REPUESTOS- BAM1020	Nozzle Adjustment Shim Kit. 8235/8236 Shims Only.	BX-310	8	$ 681.613	19%	$ 129.507	$ 6.488.960
11	REPUESTOS- BAM1020	Rubber Leak Test Nozzle Seal Tool	7440	8	$ 138.165	19%	$ 26.251	$ 1.315.330
12	REPUESTOS- BAM1020	Flow Inlet Adapter Kit (Leak Test Valve) Includes short inlet tube adapter.	BX-305	3	$ 831.292	19%	$ 157.945	$ 2.967.713
13	REPUESTOS- BAM1020	Zero Filter Calibration Kit, with leak check valve. Required for PM2.5 FEM monitoring. Same as BX-305 but with 0.2 micron filter.	BX-302	16	$ 3.981.451	19%	$ 756.476	$ 75.806.833
14	REPUESTOS- BAM1020	Pump, Gast, Rotary Vane, 100/115 VAC, 50/60 Hz	BX-121	3	$ 8.588.790	19%	$ 1.631.870	$ 30.661.979
15	REPUESTOS- BAM1020	Medo Pump Rebuild Kit, Piston, filters	680839	8	$ 1.750.088	19%	$ 332.517	$ 16.660.843
16	REPUESTOS- BAM1020	Pump Controller (Relay Module Only) Medo/GAST	BX-839	3	$ 2.528.878	19%	$ 480.487	$ 9.028.094
17	REPUESTOS- BAM1020	Automatic Flow Controller	BX-961	5	$ 6.169.523	19%	$ 1.172.209	$ 36.708.659
18	REPUESTOS- BAM1020	Filter Temperature and RH sensor KIT	BX-962	5	$ 3.327.471	19%	$ 632.219	$ 19.798.452
19	REPUESTOS- BAM1020	Filter RH Sensor Replacement Only	9278	3	$ 1.155.058	19%	$ 219.461	$ 4.123.559
20	REPUESTOS- BAM1020	Filter Temperature Sensor Replacement Only	9279	3	$ 1.155.058	19%	$ 219.461	$ 4.123.559
21	REPUESTOS- BAM1020	O-Ring, Nozzle	720066	16	$ 11.514	19%	$ 2.188	$ 219.222
22	REPUESTOS- BAM1020	Nozzle Rebuild Kit, with parts and tools	80355	3	$ 1.522.577	19%	$ 289.290	$ 5.435.600
23	REPUESTOS- BAM1020	O-Ring, Inlet Tube Receiver, 2 required.	720069	16	$ 27.633	19%	$ 5.250	$ 526.132
24	REPUESTOS- BAM1020	O-Ring Kit, Inlet Tube Receiver and Nozzle.	9122	16	$ 165.798	19%	$ 31.502	$ 3.156.791
25	REPUESTOS- BAM1020	Pump Tubing, Clear, 10mm O.D., 6.5mm I.D. Polyurethane, 25 foot roll standard	960025	8	$ 328.142	19%	$ 62.347	$ 3.123.908
26	REPUESTOS- BAM1020	Fuse, 3.15A, 250V, 5x20mm, 2 Required	590811	16	$ 27.633	19%	$ 5.250	$ 526.132
27	REPUESTOS- BAM1020	Motor, with gear box, 4 RPM. 4 per unit.	8105-1	5	$ 1.501.392	19%	$ 285.264	$ 8.933.281
28	REPUESTOS- BAM1020	PM2.5 Very Sharp Cut Cyclone, BGI Inc. VSCC™ Valid for PM2.5 FEM monitoring	BX-808	3	$ 1.299.671	19%	$ 246.937	$ 4.639.825
29	REPUESTOS- BAM1020	Waterproof Inlet Tube Sealing Gland Only	8119	3	$ 525.027	19%	$ 99.755	$ 1.874.345
30	REPUESTOS- BAM1020	Roof Top Flange Weldment Only	8120	3	$ 727.668	19%	$ 138.257	$ 2.597.776
31	REPUESTOS- BAM1020	Smart Heater UPGRADE KIT 115 VAC	9307	3	$ -	19%	$ -	$ -
32	REPUESTOS- BAM1020	O-Rings, BX-807 SCC Cyclone, set of 6	720097	8	$ 294.752	19%	$ 56.003	$ 2.806.037
33	REPUESTOS- BAM1020	O-Rings, PM10 Head, set of 3	8965	8	$ 165.798	19%	$ 31.502	$ 1.578.396
34	REPUESTOS- BAM1020	592 Ambient Temperature Sensor, Auto ID	BX-592	3	$ 5.313.821	19%	$ 1.009.626	$ 18.970.342
35	REPUESTOS- BAM1020	593 Ambient Relative Humidity Sensor, Auto ID	BX-593	3	$ 7.833.949	19%	$ 1.488.450	$ 27.967.197
36	REPUESTOS- BAM1020	594 Ambient Barometric Pressure Sensor, Auto ID	BX-594	3	$ 6.839.162	19%	$ 1.299.441	$ 24.415.807
37	REPUESTOS- BAM1020	596 AT/BP Combo Sensor, -40 +55C.; 596-1 AT/BP/RH Combo Sensor, -50 +50C.;596+ AT/BP/RH Combo Sensor, -50 +70C.	BX-596; BX-596-1 ;BX/596+	3	$ 12.625.507	19%	$ 2.398.846	$ 45.073.060
38	REPUESTOS- BAM1020	MOTHER BOARD PARA EQUIPO MET ONE, BAM 1020; Serial: R19663	3230-8	1	$ -	19%	$ -	$ -
39	REPUESTOS- BAM1020	MOTHER BOARD PARA EQUIPO MET ONE, BAM 1020; Serial: 44911	3230-8	1	$ -	19%	$ -	$ -
40	REPUESTOS- BAM1020	MOTHER BOARD PARA EQUIPO MET ONE INSTRUMENTS/Modelo: BAM1020/Serial: P20233	3230-8	1	$ -	19%		
41	REPUESTOS- BAM1020	Ciclón VSCC-A para PM2.5 (PM2.5 Very Sharp Cut Cyclone, BGI Inc. VSCC™ Valid for PM2.5 FEM monitoring)	BX-808	1	$ 12.526.949	19%	$ 2.380.120	$ 14.907.070
							TOTAL	**$ 500.190.279**

Nota 1 : Para realizar la cotización se debe revisar el documento "ANEXO N° 1: REQUERIMIENTOS PARA COTIZAR ".

Nota 2: La cotización deberá presentarse en PDF debidamente firmado por el Proponente o Representante Legal, así mismo, en Formato Excel, con valores redondeados y sin decimales.

CALOR ALBERTO BORJA HOYOS
REPRESENTANTE LEGAL

20/09/2024
FECHA

Proyectó: Johnn Christian Diaz Rojas. Contratista DLIA-CAR
Proyectó: David Santiago Arévalo Monroy. Contratista DLIA-CAR
Revisó: Luis Alfredo Zarate Vasquez. Funcionario DLIA-CAR
Revisó: Hugo Enrique Sáenz Pulido. Contratista DLIA-CAR